

MOUNT JOY BOROUGH

SIDEWALK AND CURB TRENCH RESTORATION GUIDELINES

1. At or near completion of the curb and sidewalk replacement project, Borough employees will mark areas to be sawcut and prepared for trench restoration.
2. The contractor is responsible to sawcut marked areas, remove existing asphalt and subbase to a depth of 6 inches or as directed by Borough Staff.
3. The trench will then be compacted with jump-jack type tamper.
4. This prep. work will be completed in a timely manner so that the Borough can place the asphalt for final restoration.
5. If the work is not completed in a timely manner, the Borough will perform the work and invoice the contractor on a time and materials basis.